



City of Tampa

Jane Castor, Mayor

Contract Administration
Michael W. Chucran, Director

306 East Jackson Street, 4N
Tampa, FL 33602

Office (813) 274-8116

Fax: (813) 274-7368

ADDENDUM 1

Via E-Mail

DATE: November 29, 2021

Contract 21-C-00038; Palma Ceia Wastewater Collection System Sewer Rehabilitation by CIPP

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: The Bid Opening date is here by changed to December 7, 2021.

Item 2: Replace Proposal page P-2 with the attached Proposal page P-2R.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor

**Contract; 21-C-00038
Palma Ceia Wastewater Collection System
Rehabilitation by CIPP Lining**

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words		Total
				Unit Price	one hundred thousand dollars	
100	Contingency	LS	1	\$100,000.00		\$100,000.00
102	Maintenance of Traffic	LS	1			
0408.2360	Cured in Place Pipe for 8" Dia. Gravity Sewer (.236 inch thick)	LF	55,828			
0412.2950	Cured in Place Pipe for 12" Dia. Gravity Sewer (.295 inch thick)	LF	1,151			
0424.472	Cured in Place Pipe for 24" Dia. Gravity Sewer (.472 inch thick)	LF	3,849			
0601.08	Hydraulic Cleaning & Inspection of 8" Dia. Gravity Sewer	LF	55,728			
0601.12	Hydraulic Cleaning & Inspection of 12" Dia. Gravity Sewer	LF	1,151			
0601.24	Hydraulic Cleaning & Inspection of 24" Dia. Gravity Sewer	LF	3,849			
0621	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer , 8" Dia.	LF	100			
0700	Additional Cleaning & Inspection of Gravity Sewer	LF	500			
0700	Disposal of Debris	CY	150			
2050	Reconnect Service Connections	EA	259			
2051.08	Chemical Grout Unit - chemical grout lateral post liner install - 8-inch gravity pipe diameter	EA	225			
2051.12	Chemical Grout Unit - chemical grout lateral post liner install - 12-inch gravity pipe diameter	EA	5			
2051.24	Chemical Grout Unit - chemical grout lateral post liner install - 24-inch gravity pipe diameter	EA	29			
4800	Manhole Rehabilitation by Coating System min. 250 mils thickness	SF	17,000			
4600.1p	Small Size manhole frame and cover replacement (in pavement)	EA	50			
9000	Sewer Bypass with Tanker Truck	HRS	50			
9050.08	Sewage Bypass Pumping for 8" Dia. Sewer	LF	55,728			
9050.12	Sewage Bypass Pumping for 12" Dia. Sewer	LF	1,151			
9050.24	Sewage Bypass Pumping for 24" Dia. Sewer	LF	3,849			
						TOTAL