



**City of Tampa**  
*Jane Castor, Mayor*

**Contract Administration**

306 East Jackson Street, 4N  
Tampa, FL 33602

Fax: (813) 274-7368

**ADDENDUM 2**

**Via E-Mail**

**DATE: May 5, 2023**

Contract: 22-C-00008; Sulphur Springs K-8 Various Locations – Safe Routes to School

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Replace pages P-2 and P-3 with the attached pages P-2R and P-3R.

Note: Refer to page 4 of 4 of the Water Department (Waterline Relocation Plans) for the Summary of Waterline Relocation Quantities.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to [ContractAdministration@tampagov.net](mailto:ContractAdministration@tampagov.net).

*Jim Greiner*

Jim Greiner, P.E., Contract Management Supervisor

**Contract: 22-C-00008**  
**Sulphur Springs K-8 Various Locations - Safe Routes to School FDOT LAP**  
**FPID: 443582-1-58-01**

**200-Roadway**

PAY ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST in WORDS	UNIT COST	TOTAL COST
0100	CONTINGENCY	LS	1	FIFTY THOUSAND	\$50,000	\$50,000
0101 1	MOBILIZATION	LS	1			
0102 1	MAINTENANCE OF TRAFFIC	LS	1			
0102 4	PEDESTRIAN SPECIAL DETOUR	SY	56			
0102 60	WORK ZONE SIGN	ED	7604			
0102 74 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6800			
0102 74 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	19440			
0102 99	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	320			
102115	Type III Barricade	ED	640			
01029 13 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	408			
01029 13 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	296			
0104 10 3	SEDIMENT BARRIER	LF	276			
0104 18	INLET PROTECTION SYSTEM	EA	13			
0110 1 1	CLEARING & GRUBBING	AC	0.25			
0110 4 10	REMOVAL OF EXISTING CONCRETE	SY	541			
0120 1	REGULAR EXCAVATION	CY	57			
0120 6	EMBANKMENT	CY	76			
285715	OPTIONAL BASE, BASE GROUP 15	SY	317			
0327 70 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	1501			
0334 2 1	SUPERPAVE ASHALTIC CONCRETE TYPE S-1	TN	33.2			
0334 2 3	SUPERPAVE ASHALTIC CONCRETE TYPE S-1	TN	93.1			
0400 0 11	CONCRETE CLASS NS, GRAVITY WALL	CY	4.4			
0400 0 13	CONCRETE CLASS NS, STEPS	CY	2			
0425 1021	INLETS, CURB, CITY OF TAMPA TYPE 2, <10'	EA	3			
0425 1031	INLETS, CURB, CITY OF TAMPA TYPE BS-1, <10'	EA	1			
0425 1041	INLETS, DT BOT, CITY OF TAMPA, TYPE E, <10'	EA	1			
0425 5	MANHOLE, ADJUST	EA	6			
430175115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	24			
430175118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	69			
430175215	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 15"S/CD	LF	46			
0430963 1	PVC PIPE FOR BACK OF SIDEWALK, 4"	LF	26			
0515 1 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	60			
0520 1 10	CONCRETE CURB & GUTTER, TYPE F	LF	247			
0520 2 4	CONCRETE CURB, TYPE D	LF	191			
0520 1 22	COT STANDARD (MIAMI CURB)	LF	462			
0522 1	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	205			
0522 2	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	461			
0527 2	DETECTABLE WARNINGS	SF	379			
0570 1 2	PERFORMANCE TURF, SOD	SY	657			
					TOTAL	

**Contract: 22-C-00008**  
**Sulphur Springs K-8 Various Locations - Safe Routes to School FDOT LAP**  
**FPID: 443582-1-58-01**

**300-Signing & Pavement Markings**

PAY ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST in WORDS	UNIT COST	TOTAL COST
0700 1 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	16			
0700 1 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1			
0700 1 50	SINGLE POST SIGN, RELOCATE	AS	3			
0700 1 60	SINGLE POST SIGN, REMOVE	AS	6			
0700 3101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2			
0700 13 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	17			
0706 1 3	RAISED PAVEMENT MARKER, TYPE B	EA	16			
0711 11123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	665			
0711 11125	THERMOPLASTIC, STD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	99			
0711 11130	THERMOPLASTIC, STANDARD, WHITE, VERTICAL DEFLECTION MARKING	EA	3			
0711 11140	THERMOPLASTIC, STANDARD, WHITE, VERTICAL DEFLECTION MARKING ADVANCE WARNING	EA	3			
0711 11160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1			
0711 14125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	683			
0711 16101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.091			
TOTAL						

**300-Signing & Pavement Markings**

**700-Utilities**

PAY ITEM #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST in WORDS	UNIT COST	TOTAL COST
EXC WATER	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER	LS	1			
TOTAL						

ROADWAY, SIGNING & PAVEMENT MARKING and UTILITIES - TOTAL: